



MCPS RADON TESTING – EXECUTIVE SUMMARY

Site Name	Judith A. Resnik Elementary School
Date of Test Report	4/26/2022
Round of Testing	Initial Follow-up Post Remediation 2 Year Testing 5 Year Testing HVAC Upgrade Window Replacement New Addition New Facility
# Rooms Tested	74
# Rooms \geq 4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	1.9 pCi/L

Project Status:
Initial testing completed; no further action needed.



April 26, 2022

Brian T. Croyle, PG, CHMM
Environmental Specialist
Montgomery County Public Schools
Gaithersburg, MD 20879

Re: **Radon Testing Services**
KCI Job # 122108316

Location: Judith A. Resnik Elementary School
7301 Hadley Farms Drive
Gaithersburg, MD 20879

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a “short-term” 3 day radon test for the Judith A. Resnik ES, located at 7301 Hadley Farms Dr. Gaithersburg, MD 20879 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from <https://www.montgomeryschoolsmd.org> or www.epa.gov/radon.

KCI visited the site on February 28, 2022 and deployed eighty six (86) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on March 3, 2022 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a

NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

These tests represent:

- Follow-up to initial testing.

These tests were conducted to:

- Evaluate radon concentration levels at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the 20s and high temperatures ranged from the high 50s to the low 60s Fahrenheit. Maximum sustained winds ranged from 9-17 miles per hour. Average humidity was around 40% with 0 inches of precipitation (rain) was recorded during testing period.

Results:

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 pCi/L	None	N/A
<4.0 pCi/L	See Attachment B	

Quality Control Samples	
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of

	less than the laboratory detection limit of 0.3 pCi/L.
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved.
Spike Sample Analysis:	The Spike Sample analysis results indicate the laboratory is operating within statistical control limits.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,



Tyler P. McCleaf
Radon Measurement Provider
#111004 RT
KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations
 B- Table 1-3, Radon Test Summary Spreadsheets
 C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Check, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

OC- Quality Control

Table 1- Radon Testing Results		
Judith A. Resnik ES		
Test Period: 02/28/2022 - 03/03/2022		
Kit Number	Room / Area	Result
11123392	2	< 0.3
11123384	3	1.4
11123376	4	< 0.3
11123375	5	1.0
11123383	6	0.7
11123167	7	< 0.3
11131202	7	0.6
11131216	7	0.8
11123378	8	1.2
11123336	9	0.8
11123361	10	1.2
11123377	11	1.3
11123386	12	1.0
11123388	13	1.0
11123369	14	0.9
11131220	14	0.9
11123400	15	1.1
11123359	16	1.3
11123382	17	1.0
11123395	18	< 0.3
11131206	19	1.7
11131209	20	0.9
11131219	21	0.6
11131211	22	1.2
11131221	24	0.5
11131208	25	< 0.3
11123390	26	1.1
11123368	27	0.8
11123169	28	< 0.3
11131204	29	0.7
11131203	30	< 0.3
11123175	31	< 0.3
11131215	32	< 0.3
11123166	33	0.6
11123184	34	< 0.3
11123185	34	0.8
11123180	35	< 0.3
11123181	35	< 0.3
11123182	36	< 0.3
11123398	38	0.9
11123399	39	< 0.3
11123290	40	< 0.3

Table 1- Radon Testing Results		
Judith A. Resnik ES		
Test Period: 02/28/2022 - 03/03/2022		
Kit Number	Room / Area	Result
11131205	41	0.9
11123287	42	0.9
11131212	43	1.0
11131213	43	0.8
11131214	43	< 0.3
11131210	22 OFFICE	0.6
11131217	2E	< 0.3
11123186	34 OFFICE	< 0.3
11123179	35 OFFICE	< 0.3
11123170	AA26	0.7
11123176	AA26	< 0.3
11123177	AA26	< 0.3
11123168	AP	< 0.3
11123187	APR	0.8
11123188	APR	0.7
11123178	BSM	< 0.3
11123191	COMMUNICATION	0.7
11123394	CONFERENCE	< 0.3
11123190	CONTROL ROOM	< 0.3
11123360	COU	< 0.3
11123396	HR	< 0.3
11123387	HR OFFICE	1.9
11123389	ISOLATION HR	< 0.3
11123391	K1	0.5
11123385	K2	< 0.3
11123162	K3	< 0.3
11123393	K3	0.6
11115094	K4	< 0.3
11123397	K5	< 0.3
11123183	KITCHEN OFFICE	< 0.3
11123299	MAIN OFFICE	< 0.3
11107386	MC	< 0.3
11123189	MC	< 0.3
11123195	MC	< 0.3
11123196	MC	0.5
11123194	MP	< 0.3
11123193	PHONE ROOM	< 0.3
11123197	PRINCIPAL	< 0.3
11123362	RESOURCE OFFICE	0.9
11123160	STAFF LOUNGE	1.0
11123174	STAFF LOUNGE	< 0.3
11123192	STG	0.7

Table 1- Radon Testing Results		
Judith A. Resnik ES		
Test Period: 02/28/2022 - 03/03/2022		
Kit Number	Room / Area	Result
11131207	TELEPHONE	< 0.3
11123289	WR	< 0.3

Table 2- Radon Testing Results			
Judith A. Resnik ES			
Test Period: 02/28/2022 - 03/03/2022			
Kit Number	QC Type	Room / Area	Result
11123162	D	K3	< 0.3
11131216	D	7	0.8
11123167	FB	7	< 0.3
11123369	D	14	0.9
11131212	D	43	1.0
11131214	FB	43	< 0.3
11123160	D	Staff lounge	1.0
11123176	D	AA26	< 0.3
11123177	FB	AA26	< 0.3
11123181	D	35	< 0.3
11123195	D	MC	< 0.3
11107386	FB	MC	< 0.3
11130811	OB	OFFICE BLANK	< 0.3
11130816	TB	TRAVEL BLANK	< 0.3

Summary of Missed Locations		
Judith A. Resnik ES		
Test Period: 02/28/2022 - 03/03/2022		
Kit Number	Room/Area	Result
	NA	

Summary of Missing, Compromised and >= 4 piC/L Tests		
Judith A. Resnik ES		
Test Period: 02/28/2022 - 03/03/2022		
Kit Number	Room/Area	Result
	NA	

Table Note:
* Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

March 8, 2022

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:
JUDITH A. RESNIK
MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11131220	14	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	0.9 ± 0.4	2022-03-08
11131206	19	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	1.7 ± 0.4	2022-03-08
11131209	20	2022-02-28 @ 9:00 am	2022-03-03 @ 11:00 am	0.9 ± 0.4	2022-03-08
11131219	21	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	0.6 ± 0.4	2022-03-08
11131211	22	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	1.2 ± 0.4	2022-03-08
11131210	22 OFFICE	2022-02-28 @ 9:00 am	2022-03-03 @ 11:00 am	0.6 ± 0.4	2022-03-08
11131221	24	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	0.5 ± 0.3	2022-03-08
11131208	25	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11131204	29	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	0.7 ± 0.3	2022-03-08
11131217	2E	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11131203	30	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11131215	32	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11131205	41	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	0.9 ± 0.4	2022-03-08
11131212	43	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	1.0 ± 0.4	2022-03-08
11131214	43	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	< 0.3	2022-03-08
11131213	43	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	0.8 ± 0.4	2022-03-08
11131216	7	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	0.8 ± 0.4	2022-03-08
11131202	7	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	0.6 ± 0.4	2022-03-08
11131207	TELEPHONE	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08

Radon test result report for:
JUDITH A. RESNIK
MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11123361	10	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	1.2 ± 0.4	2022-03-08
11123377	11	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	1.3 ± 0.4	2022-03-07
11123386	12	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	1.0 ± 0.3	2022-03-07
11123388	13	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	1.0 ± 0.3	2022-03-08
11123369	14	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	0.9 ± 0.4	2022-03-08
11123400	15	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	1.1 ± 0.4	2022-03-08
11123359	16	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	1.3 ± 0.4	2022-03-08
11123382	17	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	1.0 ± 0.4	2022-03-08
11123395	18	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	< 0.3	2022-03-08
11123392	2	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	< 0.3	2022-03-08
11123390	26	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	1.1 ± 0.4	2022-03-08
11123368	27	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	0.8 ± 0.3	2022-03-08
11123169	28	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123384	3	2022-02-28 @ 9:00 am	2022-03-03 @ 11:00 am	1.4 ± 0.4	2022-03-08
11123175	31	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123166	33	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	0.6 ± 0.3	2022-03-08
11123185	34	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	0.8 ± 0.4	2022-03-08
11123184	34	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123186	34 OFFICE	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123181	35	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-07
11123180	35	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123179	35 OFFICE	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123182	36	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123398	38	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	0.9 ± 0.3	2022-03-07
11123399	39	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	< 0.3	2022-03-08
11123376	4	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	< 0.3	2022-03-07
11123290	40	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	< 0.3	2022-03-08
11123287	42	2022-02-28 @ 9:00 am	2022-03-03 @ 11:00 am	0.9 ± 0.4	2022-03-08
11123375	5	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	1.0 ± 0.3	2022-03-07
11123383	6	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	0.7 ± 0.4	2022-03-08
11123167	7	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	< 0.3	2022-03-08
11123378	8	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	1.2 ± 0.3	2022-03-07
11123336	9	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	0.8 ± 0.3	2022-03-08
11123177	AA26	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-07
11123170	AA26	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	0.7 ± 0.3	2022-03-08
11123176	AA26	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123168	AP	2022-02-28 @ 11:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-07

Radon test result report for:
JUDITH A. RESNIK
MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11123188	APR	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	0.7 ± 0.4	2022-03-08
11123187	APR	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	0.8 ± 0.4	2022-03-08
11123178	BSM	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123191	COMMUNICATION	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	0.7 ± 0.4	2022-03-08
11123394	CONFERENCE	2022-02-28 @ 8:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123190	CONTROL ROOM	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123360	COU	2022-02-28 @ 9:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123396	HR	2022-02-28 @ 8:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123387	HR OFFICE	2022-02-28 @ 8:00 am	2022-03-03 @ 11:00 am	1.9 ± 0.4	2022-03-08
11123389	ISOLATION HR	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123391	K1	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	0.5 ± 0.3	2022-03-07
11123385	K2	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	< 0.3	2022-03-08
11123393	K3	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	0.6 ± 0.3	2022-03-07
11123162	K3	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	< 0.3	2022-03-08
11115094	K4	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	< 0.3	2022-03-07
11123397	K5	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	< 0.3	2022-03-08
11123183	KITCHEN OFFICE	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123299	MAIN OFFICE	2022-02-28 @ 8:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123189	MC	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123196	MC	2022-02-28 @ 11:00 am	2022-03-03 @ 11:00 am	0.5 ± 0.3	2022-03-08
11107386	MC	2022-02-28 @ 11:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123195	MC	2022-02-28 @ 11:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123194	MP	2022-02-28 @ 11:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123193	PHONE ROOM	2022-02-28 @ 11:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123197	PRINCIPAL	2022-02-28 @ 11:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08
11123362	RESOURCE OFFICE	2022-02-28 @ 9:00 am	2022-03-03 @ 10:00 am	0.9 ± 0.3	2022-03-07
11123174	STAFF LOUNGE	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-07
11123160	STAFF LOUNGE	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	1.0 ± 0.4	2022-03-08
11123192	STG	2022-02-28 @ 10:00 am	2022-03-03 @ 11:00 am	0.7 ± 0.4	2022-03-08
11123289	WR	2022-02-28 @ 8:00 am	2022-03-03 @ 11:00 am	< 0.3	2022-03-08

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologies, Inc. Job Number 204620

NOMINAL Conditions: Radon Conc 27.0 pCi/L Rel. Hum 50.1 % Temp. 70.0 F

Date Start: 3/18/22 Date Stop: 3/21/22 Date Start: _____ Date Stop: _____

Time Start: 0705 Time Stop: 0705 Time Start: _____ Time Stop: _____

Device No.'s: (5) Char Bags - Device No.'s: _____

11139367, 11139368, 11139371, _____

11139710, 11139717 _____

E3 Right

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Date Start: _____ Date Stop: _____ Date Start: _____ Date Stop: _____

Time Start: _____ Time Stop: _____ Time Start: _____ Time Stop: _____

Device No.'s: _____ Device No.'s: _____

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST)
Background = 7 μ R/h Elevation = 820 ft

March 30, 2022

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within $\pm 25\%$ of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11139367	SK1	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	25.9 \pm 2.1	2022-03-30
11139368	SK2	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	23.9 \pm 2.0	2022-03-30
11139371	SK3	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	25.7 \pm 2.1	2022-03-30
11139710	SK4	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	26.4 \pm 2.1	2022-03-30
11139717	SK5	2022-03-18 @ 7:00 am	2022-03-21 @ 7:00 am	24.6 \pm 2.0	2022-03-30

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

March 30, 2022

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

**RSH
MAIN**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11139726	BASEMENT	2022-03-20 @ 8:00 am	2022-03-23 @ 7:00 am	0.9 ± 0.5	2022-03-30
11139725	DINING	2022-03-20 @ 8:00 am	2022-03-23 @ 7:00 am	< 0.3	2022-03-30

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498



Radon Test Kit Chain of Custody

Project Name: MCPS Radon – March 2022 Schools

Name of Schools:

1. Marshall, Thurgood ES
2. Ridgeview MS
3. Travilah ES
4. Flower Hill ES
5. Resnik, Judith A. ES
6. Strawberry Knolls ES
7. Whetstone ES
8. Laytonsville ES
9. Stedwick ES
10. Watkins Mill ES
11. Watkins Mill HS
12. Einstein, Albert E. HS

	Date	Initials
Radon Test Kits Deployed	02/28/2022	PM
Radon Test Kits Collected	03/03/2022	PM
Radon Test Kits Shipped to Lab*	03/3/2022	PM
Radon Test Kits Received by Lab*	03/5/2022	PM

*All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759